

Lyon County Water District  
**Lamasco Pump Station Rehabilitation Project**

**ADDENDUM No. 1**

May 12, 2026

This ADDENDUM to plans, specifications and bidding documents for the subject project modifies the referenced items to the extent described herein. Items not modified by this ADDENDUM remain unchanged and in full effect. Bidders are required to acknowledge receipt of this ADDENDUM on the Bid Form.

1. Drawing: Sheet P-1 Pump Replacement Plan & Notes (Detail E)

*The Bidder/Contractor will be responsible for all installation costs to mate up the new pump with the existing Suction and Discharge pipe flanges in both locations. This may include new piping and/or fittings (as required) or demo/replacement of concrete pump pedestals. Currently, the height from top of concrete pedestal to the centerline of the 2.5" suction piping is approximately 11" (+/- 3/8"). Also, the vertical distance from the top of concrete pedestal to the existing discharge elbow flange is approximately 20". The Bidder/Contractor is responsible for verifying all dimensions and clearances as part of their pricing submission for the work. Perspective bidders and pump suppliers are encouraged to evaluate existing working conditions and/or visit the site to assess installation factors or limitations. Visits and access can be schedule with the Owner.*

END OF ADDENDUM NO. 1 TEXT  
This ADDENDUM consists of a total of 1 page.